



PROPOSED MALL LEVEL ELEVATION A scale:1:100

0 10m




## SCHEDULE OF MATERIALS:

- 1. Double glazed roof to mall colour RAL 9010.
- 2. Rendered finish Permarock Silicone Ultra K render system, curcuma 90 or equal.
- 3. Hartham park bath stone pier, coursing & jointing to match existing completed works.
- Windows to be hardwood timber framework, clear glazing with fibrous plaster head moulding painted gloss white.
- 5. New bespoke timber hardwood shopfronts with raised and fielded panels, polished finish with a polished brass or hardwood projecting cill.
- 6. Look—a—like panel windows with hardwood timber framework and fibrous plaster head and cill moulding, painted gloss white.
- 7. 102.5mm facing brickwork outer leaf with 140mm blockwork inner leaf to be render finish Permarock curcuma 90 or equal. (see item 2 above).
- 8. 102.5mm Facing brickwork both inner and outer leaf.
- 9. New feature steel railing, polyester powder coated, colour RAL 7015 (Slate grey).
- 10. Clock face colour white with black roman numerals. (Smiths or equal and approved).
- 11. Fibrous plaster arched ceiling feature at steel portal positions with wall mounted feature corbels below.



KEY PLAN scale:1:500

50m



ELEVATION B

